WELCOME

THE MEETING WILL BEGIN SHORTLY







UPNORTH REBULLD FULLERTON TO ADDISON

PUBLIC MEETING

September 9, 2021

AGENDA

Welcome (5 minutes)
Presentation (about 40 minutes)
Q&A (about 15 minutes)

If you have a question, type it into the chat box! We will try to address during the Q&A. FAQs, a recording of the meeting, and presentation slides will be added to the Project's website.

KATE SULLIVAN

Metra, Architect/Project Manager



ALDERMAN WAGUESPACK

32nd Ward



PRESENTATION

- Overview & Benefits
- The Work
- Environmental Review
- Cost & Funding
- What to Expect
- Outreach
- Q&A




OVERVIEW & BENEFITS





Replace 11 railroad bridges from Fullerton Avenue to Cornelia Avenue

Replace retaining walls from Fullerton Avenue to Addison Street along Metra's UP-N Line



OTHER IMPROVEMENTS



Shift tracks west to align with existing tracks north and south of project area



Refurbish and paint existing Lincoln/Addison bridge



Lower Roscoe and Cornelia Streets to maintain current clearance under the roadway and the CTA Brown Line



Utility work

BENEFITS



Modernized infrastructure that enhances safety, resiliency, and reliability




Improved bridge underpasses with state-of-theart lighting and ADA accessible travel paths



Increased efficiencies and reduced operating costs



Improved customer experience with increased passenger comfort and reduced potential for service disruptions



THE WORK





WHAT WILL BE CHANGING?






Existing Bridge at School Street

Example of new bridge construction from the UP-North Grace to Balmoral Project

WHAT WILL BE CHANGING?



Existing retaining walls to be replaced along Ravenswood Avenue, just north of Roscoe Street.



Recently constructed retaining walls along Ravenswood Avenue as part of the UP North Grace to Balmoral Project.

MORE EXAMPLES FROM THE UP-NORTH GRACE TO BALMORAL PROJECT






PROPOSED CONSTRUCTION STAGING: EXISTING CONDITION

BRIDGE VIEW

Existing bridges have bays for three tracks:


- 1. Southbound
- 2. Northbound
- 3. Unused 3rd bay



PROPOSED CONSTRUCTION STAGING: STAGE 1

BRIDGE VIEW


- Unused 3rd track bay demolished
- New northbound bridge constructed west of existing northbound track within railroad property
- During rush periods, trains operate on existing 2 tracks



PROPOSED CONSTRUCTION STAGING: STAGE 2

BRIDGE VIEW


- Old northbound track bridge bay demolished
- New southbound bridge constructed between existing southbound track and newly completed northbound track
- During rush periods, trains operate on existing southbound track and newly completed northbound track



PROPOSED CONSTRUCTION STAGING: FINAL CONDITION

BRIDGE VIEW

- Trains operate on new southbound and northbound bridges
- Tracks shifted west within railroad property to align with tracks north and south of the project
- Preserves room in railroad property for a potential third track at future dates




PROPOSED CONSTRUCTION STAGING: EXISTING CONDITION

EMBANKMENT VIEW




PROPOSED CONSTRUCTION STAGING: STAGE 1

EMBANKMENT VIEW




PROPOSED CONSTRUCTION STAGING: STAGE 2

EMBANKMENT VIEW




PROPOSED CONSTRUCTION STAGING: FINAL CONDITION

EMBANKMENT VIEW



UP NORTH GRACE TO BALMORAL TRACK REALIGNMENT









2012 2016 2020 2021

ENVIRONMENTAL REVIEW





ENVIRONMENTAL REVIEW

- Examine and identify potential environmental effects
- Follows National Environmental Policy Act (NEPA)
- Required for federal funding
- Federal Transit Administration determined a Documented Categorical Exclusion (DCE) is required
- Project is not expected to have a significant effect on the environment
- Environmental review started

Results of environmental analysis will be shared at 2nd public meeting


ANALYSIS AREAS

Environmental review of the following areas:

- Air quality
- Land use and zoning
- Traffic
- Construction impacts
- Historic resources
- Visual setting
- Noise and vibration
- Parks and recreation areas

- Hazardous materials
- Social and community disruption
- Environmental justice
- Wetlands, floodplains, threatened and endangered species
- Safety and security

The National Environmental Policy Act (NEPA) looks at a broad range of community and environmental impacts. It is required for all federally funded projects.



NOISE AND VIBRATION ANALYSIS

Procedure follows Federal Transit Administration Transit Noise and Vibration Impact Assessment Manual

Steps Include:


- Measure existing noise and vibration conditions
- 2. Develop and validate models
- 3. Model for proposed conditions
- 4. Evaluate for impacts
- 5. If needed, identify potential mitigation options
- 6. General assessment of constructionrelated noise



Noise monitoring within project corridor

NOISE AND VIBRATION MITIGATION OPTIONS

- Moderate or severe noise impacts require consideration of mitigation options
- Metra is committed to design the project to not result in severe noise impacts
- UP North Grace to Balmoral example:
 - Mitigation measures at one property where impacts were projected included a noise barrier wall, vibration reducing pads under the ties, and operational changes



Source: Federal Transit Administration Transit Noise and Vibration Impact Assessment Manual

COST & FUNDING





COST & FUNDING

- Total estimated cost: \$262.3M
- Included in Metra's Capital Program
- \$161.2 million is currently allocated
- Funding sources include:
 - \$6M 2019 Federal Transit Administration
 5337 State of Good Repair Funds
 - \$156.1M Rebuild Illinois Bond Funds
- Additional funding being pursued

\$156.1M

Rebuild Illinois Bond

\$6M

Federal Transit Administration


WHAT TO EXPECT





CURRENT WORK

- Early design and planning stage
- Environmental review period
- Field visits
- Data collection
- Provide information to public





ANTICIPATED GENERAL CONSTRUCTION IMPACTS

- Temporary street closures, detours, construction noise, etc.
- Presence of construction workers, equipment, and construction parking
- Anticipated disruptions will be documented during the environmental review process
- Further information will be discussed at Public Meeting #2



ADJACENT PROPERTIES

- No permanent property acquisition is anticipated
- Temporary construction access needed at properties along the railroad property line
- Some property owners will see a change in how they currently use the railroad property along the corridor






ADJACENT PROPERTIES COORDINATION

- Adjacent Property Owner Liaison
- Melody Carvajal <u>carvajalma@cdmsmith.com</u>
- Coordinating with property owners and residents where temporary property access may be needed
- Properties directly adjacent to the railroad right-ofway may contact Melody directly to begin coordination

FEATURES ALONG & IN THE RIGHT-OF-WAY





OUTREACH





PUBLIC OUTREACH

- Adjacent Resident Liaison Melody Carvajal carvajalma@cdmsmith.com
- Project Email for comments UPNrebuild@metrarr.com
- Email List
 - Neighbors, Community Members
 - Community Groups
 - Neighborhood Organizations
 - Homeowner / Condo Associations
- Public Meetings





- Continued design development and environmental review
- Coordination with adjacent property owners, Aldermen's offices, condo associations, and community groups



QSA

If you have a question, type it into the chat box! We will try to address it during this time.

If you have comments, please email us at <u>upnrebuild@metrarr.com</u>.

REACH OUT TO US!

Website: metra.com/upnrebuild

Email: upnrebuild@metrarr.com

FAQs, a recording of the meeting, and presentation slides will be added to the Project's website.

For media inquiries, please contact Michael Gillis at mgillis@metrarr.com.



THANK YOU!

Questions



